



Jeff Quinn
3412 N. Janney Ave.
Muncie, IN 47304
(765) 730-2468

**Job Address: 3809 N. Lanewood Dr.
Muncie, IN, 47304**

ROOF REPLACEMENT ESTIMATE

Job Description:

- Remove existing shingles, felt paper, and drip edge exposing bare plywood
- Inspect all plywood for damaged or rotten wood, and replace 6 apparent bad sheets of plywood
- Apply new 15 pd. Felt paper to entire roof
- Apply new wicker aluminum drip edge roof starter
- Install new Land/Mark Certainteed dimensional shingles of homeowners choice of color to entire roof
- Install new roof vents, and pipe boots
- Apply roof cement/cyclone to any areas prone to water leakage
- Remove and clean any debris in gutters
- Clean up and haul away all material removed from the roof
- Cut in, and install 12 soffit vents(6 front & 6 back)

Material And Dumpster \$2565.00

Labor \$1860.00

Total Job Cost \$4425.00